



Possible widening of channel by removing hedge and excavating within the field from the left bank. (For typical section see Appendix A.14). Construction of raised bunds to contain design flow.

Enlargement of Sea Cut Outfall, (currently egg shaped 1.6m wide, 1.1m high) encompassing steps for wildlife. For Q50 propose 1.5 x capacity, Q100/Q200 propose 2 x capacity. Invert 38.4m AOD.

- Legend:
-  Modelled Watercourses
 -  Channel Widening
 -  Cross Section Location/Chainage
 -  Sea Cut Outfall



Project Title:
Church Beck PAR

Figure Title:
Location of Measure 5 Channel Widening

Document Reference: **5002531/98/DG/54** Figure Number: **Appendix A.11**

